

UNCLASSIFIED

AD NUMBER

ADB022525

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.

FROM:

Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; 12 AUG 1977. Other requests shall be referred to Electronics Systems Division, Attn: AFSC, Hanscom AFB, MA 01731.

AUTHORITY

USAFGL ltr, 7 Sep 1982

THIS PAGE IS UNCLASSIFIED

AD B 022525

AUTHORITY: USAFGL

1tr 7 Sep 82





E-SYSTEMS
Montek Division



Report No. 131500-616
12 August 1977



ADB022525

LOW PRESSURE ALTITUDE TEST REPORT
FOR THE
AN/TRN-41 TACAN NAVIGATIONAL SET

Distribution limited to U. S. Government agencies only;
Reason: Test and Evaluation. 12 August 1977. Other
requests for this document must be referred to
Department of the Air Force, Headquarters Electronic
Systems Division (AFSC), Hanscom Air Force Base,
Massachusetts 01731, Attention: RRG.

Prepared for:
Department of the Air Force
Headquarters Electronic Systems Division (AFSC)
Hanscom Air Force Base
Massachusetts 01731

Prepared by:
E-Systems, Inc., Montek Division
2268 South 3270 West
Salt Lake City, Utah 84119

Contract No. F19628-75-C-0200
CDRL Item A00Y



AD No. _____
DDC FILE COPY

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER ESD-TR-77-313	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER	
4. TITLE (and Subtitle) LOW PRESSURE ALTITUDE TEST REPORT FOR THE AN/TRN-41 TACAN NAVIGATIONAL SET		5. TYPE OF REPORT & PERIOD COVERED	
7. AUTHOR(s) None		6. PERFORMING ORG. REPORT NUMBER 14 131500-616	
		8. CONTRACT OR GRANT NUMBER(s) F19628-75-C-0501	
9. PERFORMING ORGANIZATION NAME AND ADDRESS E-Systems, Inc., Montek Division 2268 South 3270 West Salt Lake City, Utah 84119		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS Electronic Systems Division (AFSC) Hanscom AFB Ma. 01731		12. REPORT DATE 12 August 1977	
		13. NUMBER OF PAGES 12 18P.	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS (of this report) Unclassified	
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A	
DISTRIBUTION STATEMENT (of this Report)			
16. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) Distribution limited to U.S. Government agencies only; Reason: Test and Evaluation. 12 August 1977. Other requests for this document must be referred to Department of the Air Force, Hq ESD (AFSC) Hanscom AFB Ma. 01731 Attention: DRI			
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) AN/TR-41 TACAN NAVIGATIONAL SET			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report describes the low pressure test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TR-41.			

408354

LOW PRESSURE ALTITUDE TEST REPORT
for the
NAVIGATIONAL SET, TACAN, AN/TRN-41

This report describes the low pressure test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41, 131500-415.

1. **Test Identification.** Low pressure test as defined in Appendix IV-C (low pressure test procedure) of the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41.
2. **Functional Purpose of Test.** This test forms a part of the AN/TRN-41 system qualification tests.
3. **Test Objectives.** To demonstrate that the AN/TRN-41 will meet the low pressure requirements of paragraphs 3.2.5.1.3 and 4.2.1.4.3.4 of Specification No. 404L-701-5017A, Part 1 of 2 parts (20 August 1976).
4. **Description of Test Articles.** The AN/TRN-41 system consisting of the following was used for the tests:

Receiver-Transmitter	RT-1202/T
Antenna	AS-3132/T
Antenna Support	AB-1237/T
Filter, DC Power	F-1439/T
Interconnecting Cables	

ACCESS	File Section <input type="checkbox"/>	BY INSTRUCTIONAL FACULTY COPIES	DATE
NTIS	B. H. Section <input checked="" type="checkbox"/>		
DOC	<input type="checkbox"/>		
UNANNOUNCED			
JUSTIFICATION			
		Date	B

5. **Summary of Test Results.** The AN/TRN-41 showed no functional or physical degradation during the low pressure test.
6. **Description of Test Facilities and Procedures.** The test facilities and test procedures are described in Appendix IV-C of the Equipment Test Plan.
7. **Test Setup Diagrams.** The test setup diagrams are provided in Appendix IV-C of the Equipment Test Plan.

8. **Test Equipment.** See Attachment 1 for test equipment used for the low pressure test and the pretest, test and post test operational tests.

9. **Test Data.** Attachment 2 contains the data sheets for the low pressure test and the pretest, test and post test operational tests.

10. **Test Conditions.** The system was maintained at a pressure equivalent to an altitude of 45,000 feet for 1 hour. The pressure was then increased to an altitude of 13,100 feet and the system operated at that pressure.

11. **Test Results Analysis.** The system operated normally during the low pressure tests and comparison of test data showed that no degradation of performance occurred during the test. No physical degradation was observed in the visual inspection.

12. **Certification.** The data sheets shown in Attachment 2 have been signed by a Montek Quality Assurance representative and a DCAS representative, certifying that the test results are authentic, accurate, current and in accordance with the related test plan.

ATTACHMENT 1
TEST EQUIPMENT

TEST EQUIPMENT

<u>Description/Manufacturer</u>	<u>Model</u>	<u>Calibration Due Date</u>
Oscilloscope, Tektronix	465	7/6/77
Signal Generator, RF, H.P.	612A	6/23/77
Peak Power Meter, Boonton	8900B	9/19/77
Pulse Generator, Data Pulse	110B	5/12/77
Counter, Fluke	1953	8/12/77
Half-Ampl. Det. Montek	131500-702	N/A
RF Detector, Montek	135203-100	N/A
Monitor Ant., Montek	006300	N/A
Test Box - Interconnection - Montek	131500-703	N/A
Power Supply HP	6274B	1/16/78
Power Supply Acopian		12/9/77
Power Supply, Sorensen	QR4075A	9/19/77
Directional Coupler 20 dB, Narda	3042B	N/A
Directional Coupler 10 dB, Microlab	CBA-78	N/A
Variable Attenuator, Weinschel 0-10 dB	905	N/A
RF Attenuator, Weinschel	10 dB	N/A
Multimeter, Fluke	8120A	8/2/77
Altitude Chamber, Sperry Univac	-	N/A
Electronic Monometer, Datametric	1023A	10/7/77
Temperature Controller, Honeywell	152P1-92-111-74	10/7/77

ATTACHMENT 2
DATA SHEETS

APPENDIX IV-K
DATA SHEET
ENVIRONMENTAL TEST

131500-415

June 30, 1976

TEST Low Pressure (Altitude)
SYSTEM 002

from 9 May 1977
DATE to 9 May 1977
ACCEPTABLE X
NOT ACCEPTABLE _____

RE MARKS The system was subjected to the low pressure (altitude) tests as outlined by test procedure 131500-415, appendix IV-C. At the conclusion of the low pressure test, the system operated normally. There was no degradation in performance based on comparison of test data. No discrepancies were noted.

DISCREPANCIES

SIGN OFF INFORMATION

ENVIRONMENTAL TEST ENGINEER _____

DATE _____

REPRESENTATIVE ENGINEER B.D. Taylor

DATE 5-11-77

QA REPRESENTATIVE M. B. Quint

DATE 5-11-77

DCASD OR AF CONCURRENCE Walt R. Clark

DATE 5-11-77

DATA SHEET
OPERATIONAL TESTS
AN/TRN-41

June 30, 1976

BEST AVAILABLE COPY

Test ALTITUDE - (LOW PRESSURE

Date 5/8/77

System 003

Time 10:45

Tech

Para. No.	Description	5/8/77 The Test max	Test	Post Test	Requirements	Units
6.1	Calibrated RF insertion loss $P_L = 31.2$ dB Used in determining RF peak power.	N/A	N/A	N/A	N/A	N/A
6.2	System turn on normal operation	✓	✓	✓	Check if OK	N/A
6.3.1	Antenna radiated signal 15 Hz	✓	✓	✓	Check if OK	N/A
	135 Hz	✓	✓	✓	Check if OK	N/A
6.3.2	Antenna Speed	66.667	66.669	66.667	66.667 ± .133	ms
6.4.1.1	Correct identity code	✓	✓	✓	Check if OK	N/A
6.4.1.2	Identity period	37.5	38.0	38.0	37.5 ± 3.75	Seconds
6.4.2	Peak power (1) Reading of peak power meter $P_m =$ (2) Convert to dBm - $10 \log$ $P_m \times 10^3 = P_m \text{ dBm}$ Total power output in dBm $P_{m \text{ dBm}} + P_L =$ *Insertion loss see 6.1 above.	76mw 18.8 dBm	76mw 18.81 dBm	76mw 18.81 dBm	N/A N/A	Watts dBm
6.4.3.3	Pulse count	7184	7182	7187	7200 ± 180	Counts
6.4.4.2	Pulse shape Width (50%) Rise time (10-90%) Fall time (90-10%)	3.6μs 2.2μs 2.5μs	3.6μs 2.2μs 2.5μs	3.6μs 2.2μs 2.5μs	3.5 ± 0.5 2 ± 0.25 2.5 ± 0.5	μs μs μs
6.4.4.4	Pulse spacing	12.0μs	12.0μs	12.0μs	12.0 ± 0.1	μs
6.4.5.2	Delay - 60 ± 10 μs 15 Hz trig to first burst pulse.	✓	✓	✓	Check if OK	

June 30, 1976

DATA SHEET
OPERATIONAL TESTS
AN/IRN-41 (Continued)

No.	Description	Pre Test	Test	Post Test	Requirements	Units
4.5.3	Correct north burst - 12 pulse pairs spaced $30 \pm 0.1 \mu s$	✓	✓	✓	Check if OK	
4.5.5	Delay $50 \pm 10 \mu s$ - 135 Hz trig to first burst pulse	✓	✓	✓	Check if OK	
4.5.6	Correct Aux burst - 6 pulse pairs spaced $24 \pm 0.1 \mu s$	✓	✓	✓	Check if OK	
4.5.5	RT replies to 3300 interrogations	2627	2562	2508	≥ 2310 (Counts/Second)	
4.5.7	Demand only mode - times to switch from ON to STBY within 70 seconds	✓	✓	✓	Check if OK	L
4.6.8	STBY mode	✓	✓	✓	Check if OK	
4.6.9	Demand Only mode - time to switch from STBY to ON <i>≤ 10 sec</i> <i>20</i> <i>4/19/77</i>	✓	✓	✓	Check if OK	
4.6.10	ON AIR mode	✓	✓	✓	Check if OK	
4.7.1	DME ONLY mode	✓	✓	✓	Check if OK	
4.7.2	Switch from DME to TACAN	✓	✓	✓	Check if OK	
4.8.1	Antenna Alarm - Within four seconds	✓	✓	✓	Check if OK	
4.8.2	Alarm Reset	✓	✓	✓	Check if OK	
4.8.3	RT Alarm - Within five seconds	✓	✓	✓	Check if OK	
4.8.4	Alarm Reset	✓	✓	✓	Check if OK	

BEST AVAILABLE COPY

E 3113A

FACILITY:

ENVIRONMENTAL DATA SHEET ENVIRONMENTAL LABORATORY — DEPT. 330

A-1

A.O. 298K-143

ENV. TECH. R K Davis

TEST SCHED.

ENGINEER OR O.C.M. Rogers (E systems)

PHONE 993-9300, x288

TEST COMPLETED

TECHNICIAN

PHONE

TEST REMOVED

UNIT TITLE AN/TRN-41

SER.

QTY. 1

TOTAL UTILIZATION

INSTRUCTIONS

TO

OPERATOR

TEST TO TERMINATE:

BY:

ENVIRONMENTAL
LABORATORY
SUPERVISORS
APPROVAL

TEST Low Pressure

SPEC. Mil-std 810

MIL Method 500.1

1. Test per procedure I
 - A. 3.28" Hg or 45,900 ft.
 - B. hold for 1 hr.
 - C. 16.20" Hg or 13,100 ft.
 - D. operate Test Item.
 - E. Return to Ambient pressure.

D. W. Black

SIGNATURE

DATE

DATE

TIME

CHRONOLOGICAL RECORD OF TEST

INITIALS
(PRINT)

5/9/77

Place AN/TRN-41 in Altitude chamber.
set pressure to 3.28" Hg. hold for 1 hr.

DWB

5/9/77

Reset pressure to 16.20" Hg. After stabilization.
operated Test Item

DWB

5/9/77

Return chamber to ambient pressure.

DWB

BEST AVAILABLE COPY

VERIFIED & RELEASED BY:

O.C. OR PROGRESS

COMBIZANT ENGINEER

THIS REPORT HAS BEEN DELIMITED
AND CLEARED FOR PUBLIC RELEASE
UNDER DOD DIRECTIVE 5200.20 AND
NO RESTRICTIONS ARE IMPOSED UPON
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.